

MIDDLESEX COUNTY COLLEGE

STUDIO THEATER COMPLETE BUILDING DEMOLITION

BID # 18-18

CLARIFICATION # 1

JUNE 22, 2017

The following are clarifications of the Specifications and Drawings and are considered to be a part of the Bid Documents:

Item # 1

No change in Bid Date and Time.

Item # 2

The existing 3" sanitary line running from the Studio Theater to the manhole in the parking lot is collapsed. Cap existing sanitary outside the footprint of the Studio Theater, and abandon. The existing sanitary line is located adjacent to the sprinkler shut off.

Item # 3

The existing crawlspace flooring is soil / earth, it is not a below grade slab.

END OF CLARIFICATION # 1